

# Tape Silo Destruction & Removal Project

For Additional Information please contact:

mailto:info@discoveritsolutions.com

# **Project Attributes:**

# Description

De-install, pack and remove eight Sun / StorageTek 9310's and their associated equipment from the customers data center. Provide green disposal and recycling of all materials. Provide a Certificate of Green Recycling for each piece of equipment. Hardware included:

- Library Management and Control Units
- Drive Cabinets
- Tape Robot Units
- > 9840 Drives

### Time Line

# **Day 0 Activities**

- Review tools required, pack
- Joe & Bryan Travel to customer location, arrive at hotel
- Travel to Home Depot, secure additional necessary tool items

## **Day 1 Activities**

- Disconnect ALL power to tape drive cabinets, LMU's, LCUS and LSM (silo).
- Unscrew arrays that cover bolts to drive cabinets and LCU's.
- Remove all drive cabinets, LMU's, LCU's and roll them out to the loading dock. By mid day prepare the cabinets for shipping.
- Coordinate arrival time for the flatbed truck.
- Detach all Silo entry door's and begin stacking on pallets and prep for shipping.
- Begin removing the Theta Arm Assemblies.
- Unscrew all screws and begin moving arrays to trash containers.

### Day 2 through 4 Activities

- Acquire two local workers from waste management company
- Begin de-install of inner walls and stack on pallets.
- Ceiling panels are next. Stack for shipping.
- Remove Theta motor, arm and base and prep for shipping.
- Unscrew bolts to outer walls and stack for shipping.
- Unscrew floor bolts and stack for shipping.

### **Day 5 Activities**

- Finish remaining activities.
- Return tools to Home Depot.



































